# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35682/CALL-2

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/06/2019-20, Date: 15.06.2019**

**Drilling of Borewells providing Pump, motos and laying pipeline in Ward No. 05 Sarrounding area byatarayanapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of H V Nagaraj ( KRANTHI ELECTRICALS ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 4 | Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc (P.NO-47, I.NO-9.4, PRED 12-13 SR) | Each BW | 2025.0 | 8100.00 | Rupees Two Thousand Twenty Five Only |
| 2 | 200 | Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) (P.NO-47, I.NO-9.1, PRED 12-13 SR) 0 to 50 m | Rmtr | 329.0 | 65800.00 | Rupees Three Hundred Twenty Nine Only |
| 3 | 200 | 50 to 100 m | Rmtr | 430.0 | 86000.00 | Rupees Four Hundred Thirty Only |
| 4 | 200 | 100 to 150 m | Rmtr | 478.0 | 95600.00 | Rupees Four Hundred Seventy Eight Only |
| 5 | 200 | 150 to 200 m | Rmtr | 505.0 | 101000.00 | Rupees Five Hundred Five Only |
| 6 | 200 | 200 to 250 m | Rmtr | 585.0 | 117000.00 | Rupees Five Hundred Eighty Five Only |
| 7 | 200 | 250 to 300 m | Rmtr | 627.0 | 125400.00 | Rupees Six Hundred Twenty Seven Only |
| 8 | 280 | 300 to 370 m | Rmtr | 649.0 | 181720.00 | Rupees Six Hundred Forty Nine Only |
| 9 | 240 | Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/!993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes) (P.NO-III, I.NO-84, PRED 12-13 SR) | Rmtr | 1426.0 | 342240.00 | Rupees One Thousand Four Hundred Twenty Six Only |
| 10 | 40 | Providing and fixing 250mm dia PVC pipe and as per specification and directions. ( BWSSB SR 13-14, P.No.53 I.no.1 of sl.no.11.) | Rmtr | 1183.0 | 47320.00 | Rupees One Thousand One Hundred Eighty |
| 11 | 4 | 175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR) | Each | 107.0 | 428.00 | Rupees One Hundred Seven Only |
| 12 | 36 | M.S. Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR) | Each | 161.0 | 5796.00 | Rupees One Hundred Sixty One Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of H V Nagaraj ( KRANTHI ELECTRICALS ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 13 | 88000 | Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14) | Sqm | 0.35 | 30800.00 | and Thirty Five Paise Only |
| 14 | 180 | Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14) | no | 94.0 | 16920.00 | Rupees Ninety Four Only |
| 15 | 4 | Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR) | No | 496.0 | 1984.00 | Rupees Four Hundred Ninety Six Only |
| 16 | 12 | Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11 | No | 156.0 | 1872.00 | Rupees One Hundred Fifty Six Only |
| 17 | 120 | Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable ( confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14) | Mtr | 177.0 | 21240.00 | Rupees One Hundred Seventy Seven Only |
| 18 | 120 | Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14) | Mtr | 59.0 | 7080.00 | Rupees Fifty Nine Only |
| 19 | 12 | Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14) | Mtr | 307.0 | 3684.00 | Rupees Three Hundred Seven Only |
| 20 | 4 | Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia (P.NO - 552, I.NO - 7 , BWSSB SR 13-14) | No | 1775.0 | 7100.00 | Rupees One Thousand Seven Hundred Seventy Five Only |
| 21 | 4 | Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14) | No | 284.0 | 1136.00 | Rupees Two Hundred Eighty Four Only |
| 22 | 4 | Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14) | No | 325.0 | 1300.00 | Rupees Three Hundred Twenty Five Only |
| 23 | 4 | Borewell Cap and Clamp Set (PWD SR 2018-19, Page No. XLVII, Sl nO. 17) | Set | 1881.0 | 7524.00 | Rupees One Thousand Eight Hundred Eighty One |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of H V Nagaraj ( KRANTHI ELECTRICALS ) In Figures | | In Words |
|---|---|---|---|---|---|---|
| 24 | 4 | Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.50 HP 30 stage (P.NO-XXXXIII, I.NO-34, PWD SR 18-19) | No | 75371.0 | 301484.00 | Rupees Seventy Five Thousand Three Hundred Seventy One Only |
| 25 | 1340 | Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class (SR 18-19 PWD, P.No.XLVII Sl.no. 1 | Rmtr | 433.0 | 580220.00 | Rupees Four Hundred Thirty Three Only |
| 26 | 224 | Supply and fixing Collar for GI Pipes 50MM (Page No. XLVII, Sl NO.2, PWD SR-2018-19 | No | 188.0 | 42112.00 | Rupees One Hundred Eighty Eight Only |
| 27 | 2920 | Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19 | Mtr | 150.0 | 438000.00 | Rupees One Hundred Fifty Only |
| 28 | 4 | Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR) Page No. XLVII, Sl NO. 13, PWD SR 2018-19 | No | 21945.0 | 87780.00 | Rupees Twenty One Thousand Nine Hundred Forty Five Only |
| 29 | 4 | Supplying & delivery of brand 50mm Gate Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 15 | No | 1881.0 | 7524.00 | Rupees One Thousand Eight Hundred Eighty One |
| 30 | 4 | Supplying & delivery of brand 50mm Non Return Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 16 | No | 1881.0 | 7524.00 | Rupees One Thousand Eight Hundred Eighty One |
| 31 | 4 | Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19) | No | 940.0 | 3760.00 | Rupees Nine Hundred Forty Only |
| 32 | 8 | GI Pipe 40mm A Class, for Electrical Pole (P.NO - XLVII, SL.NO - 20, PWD SR 18-19) | Mtrs | 418.0 | 3344.00 | Rupees Four Hundred Eighteen Only |
| 33 | 4 | Pot Head (P.NO - XLVII, SL.NO - 21, PWD SR 18-19) | No | 376.0 | 1504.00 | Rupees Three Hundred Seventy Six Only |
| 34 | 72 | Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19) | Cum | 331.0 | 23832.00 | Rupees Three Hundred Thirty One Only |

Signature of the contractor



9/07
Executive Engineer
9/07

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of H V Nagaraj ( KRANTHI ELECTRICALS ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 35 | 160 | Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19) | Mtr | 412.0 | 65920.00 | Rupees Four Hundred Twelve Only |
| 36 | 72 | Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19) | Cum | 134.0 | 9648.00 | Rupees One Hundred Thirty Four Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92